

HSE TOOLBOX TALK

LOAD STABILITY AND CENTER OF GRAVITY TOOLBOX TALK**PURPOSE AND SCOPE**

Prevent rotation, shifting and instability caused by incorrect center-of-gravity assessment during lifting.

KEY HAZARDS

1  Incorrect center of gravity.	2  Uneven load distribution.	3  Sudden load rotation.	4  Rigging slippage.
5  Movement of internal liquids.	6  Incorrect lifting points.	7  Inadequate trial lift.	8  People beneath the load.

CRITICAL POINTS TO VERIFY IN THE FIELD

01 Incorrect center of gravity.	02 Uneven load distribution.	03 Sudden load rotation.
---	--	------------------------------------

**REMEMBER — SERNEM****S**

Stop and think

E

Evaluate the risk

R

Remove or reduce

N

Never assume

E

Ensure protection

M

Monitor and communicate

HSE TOOLBOX TALK

LOAD STABILITY AND CENTER OF GRAVITY TOOLBOX TALK**FIELD REQUIREMENTS AND VERIFICATION**

Prevent rotation, shifting and instability caused by incorrect center-of-gravity assessment during lifting.

SERNEM FIELD 01**FIELD VERIFICATION 1**

Load weight known

SERNEM FIELD 02**FIELD VERIFICATION 2**

Center of gravity assessed

SERNEM FIELD 03**FIELD VERIFICATION 3**

Lifting points suitable

SERNEM FIELD 04**FIELD VERIFICATION 4**

Rigging correct

VERIFICATION BEFORE START

- | | |
|--|---|
| ☐ Load weight known | ☐ Center of gravity assessed |
| ☐ Lifting points suitable | ☐ Rigging correct |
| ☐ Trial lift planned | ☐ Load behaviour monitored |

SUPERVISOR DISCUSSION POINTS

- Where is the center of gravity?
- Are lifting points suitable?
- Is the load asymmetrical?

FIELD APPLICATION

A load may appear balanced while its center of gravity is somewhere unexpected.

HSE TOOLBOX TALK

LOAD STABILITY AND CENTER OF GRAVITY TOOLBOX TALK

CRITICAL CONTROL MEASURES

1. ELIMINATE / REDUCE THE RISK

Determine load weight and center of gravity. • Observe load behaviour during the trial lift. • Stop lifting if the load is unstable.

2. ENGINEERING & PHYSICAL CONTROLS

Use approved lifting points. • Apply additional rigging control for asymmetrical loads. • Keep all personnel clear of suspended loads.

3. WORK METHOD & FIELD CONTROLS

Configure rigging around the center of gravity. • Assess movement of liquids inside equipment.

4. PPE, VERIFICATION & SUPERVISION

Perform a low-height trial lift. • Plan safe tag-line use where required.

CRITICAL WARNING



Team, we will lift according to both load weight and center of gravity. If the load is unstable during the trial lift, we will stop and re-rig.

SITE CHECKLIST — BEFORE STARTING WORK

- ☐ Load weight known

☐ Lifting points suitable

☐ Trial lift planned

☐ Asymmetry assessed

☐ Area below clear
- ☐ Center of gravity assessed

☐ Rigging correct

☐ Load behaviour monitored

☐ Liquid movement assessed

☐ Crew briefed

HSE TOOLBOX TALK

LOAD STABILITY AND CENTER OF GRAVITY TOOLBOX TALK

ATTENDANCE AND APPROVAL

Project / Site:

Date:

Presented by:

Work area:

No	Full Name	Company / Role	Signature
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			